



Athi Water Works Development Agency  
Athi Water Plaza. Muthaiga North Road. Off Kiambu Road  
P.O Box 45283 00100 Nairobi  
Tel: (+254) 20 -2724292/3. Mobile: (254) 715-688272  
E-mail info@awwda.go.ke  
www.awwda.go.ke

When replying please quote: AWWDA/GOK/ENP/W-20/2023-2024/VOL.I (12) PE-jms

8<sup>th</sup> April, 2024

**To All Bidders**

**PROCUREMENT OF WORKS FOR THE CONSTRUCTION OF WATER PROJECTS WITHIN AWWDA AREA OF JURISDICTION – PHASE II: DRILLING AND EQUIPPING OF 4NO. BOREHOLES, CONSTRUCTION OF 4NO. ELEVATED STEEL WATER TANKS AND ASSOCIATED WATER DISTRIBUTION PIPELINES IN EAST NAIROBI AREA: TENDER NO: AWWDA/GOK/ENP/W-20/2023-2024**

**CLARIFICATIONS TO ISSUED BIDDING DOCUMENT AND BID SUBMISSION FOR PROCUREMENT FOR WORKS**

Reference is made to the ongoing procurement of Works for the Drilling and Equipping of 4No. Boreholes, Construction Of 4No. Elevated Steel Water Tanks and Associated Water Distribution Pipelines in East Nairobi Area: IFB No.: AWWDA/GOK/ENP/W-20/2023-2024.

Pursuant to clauses ITT 7.1 of the Tender Data Sheet (TDS), please find attached responses to clarifications as received by 8<sup>th</sup> April, 2024.

Please note that the bid submission date remains 18<sup>th</sup> April, 2024 at 11:00 a.m. East Africa Time.

**ENG. JOSEPH KAMAU**  
**Ag. CHIEF EXECUTIVE OFFICER**

Encl.

CONSTRUCTION OF WATER PROJECTS WITHIN AWWDA AREA OF JURISDICTION – PHASE II: DRILLING AND EQUIPPING OF  
 4NO. BOREHOLES, CONSTRUCTION OF 4NO. ELEVATED STEEL WATER TANKS AND ASSOCIATED WATER  
 DISTRIBUTION PIPELINES IN EAST NAIROBI AREA



TENDER NO.: AWWDA/GOK/ENPW-20/2023-2024

RESPONSE TO CLARIFICATIONS SOUGHT BY BIDDERS

S/No.	Request for Clarification / Query	Response
1.	Bill No. 6 – SOLARIZATION OF 4NO. BOREHOLES – is missing from the BoQ although entry is present on the summary sheet.	The missing Bill No. 6 is hereby attached to this response

SIGNED: Name..... *Kiprono* ..... Sign..... *RSP* ..... 1 of 1

BILL NO. 6 - SOLARIZATION OF 4NO. BOREHOLES					
ITEM NO.	DESCRIPTION	UNIT	QTY	RATE (KSHS)	AMOUNT (KSHS)
601	Supply and installation of monocrystalline solar modules of 335W capacity capable to power submersible pumps or as directed by the Project Manager	Nr.	60		
602	Solar Inverter/Controller for 18.5kw (Hybrid)	Nr.	1		
603	PV Disconnet Switch 1000/16A	Nr.	1		
604	Changeover Switch	Nr.	1		
605	Enclouser for PV Disconnect and Controller measuring	Nr.	1		
606	Lightening Arrestor	Nr.	1		
607	Earthrod c/w clamp	Nr	1		
608	10MM2X2 SOLAR PV cable	m	100		
609	6MM2X2 SOLAR PV cable	m	100		
610	Solar Module steel support structure 3m above the ground surface with members of the following specifications: Angle line 40x40x3mm frame; SHS 50X50X3mm - horizontal and vertical beams; SHS 75x75x3mm stands; SHS 40x40x3mm bracings and MS plate 6mm thick	LS	1		
Total for Installing 1 No. Solar System					
<b>Total for 4 No. Boreholes Carried to Summary Page</b>					

02