

When replying please quote: AWWDA/GOK/GNL/W-19/2023-2024 /VOL.I (10) PE-jms

12<sup>th</sup> April, 2024

To All Bidders;

**PROCUREMENT OF WORKS FOR THE CONSTRUCTION OF WATER PROJECTS WITHIN AWWDA AREA OF JURISDICTION – PHASE II: CONSTRUCTION OF GATUNDU NORTH AND LARI WATER SUPPLY PROJECT: TENDER NO.: AWWDA/GOK/GNL/W-19/2023-2024**

**CLARIFICATIONS TO ISSUED BIDDING DOCUMENT AND BID SUBMISSION FOR PROCUREMENT FOR WORKS**

Reference is made to the ongoing procurement of Works for the Gatundu North and Lari Water Supply Project: IFB No.: AWWDA/GOK/GNL/W-19/2023-2024.

Pursuant to clauses ITT 7.1 of the Tender Data Sheet (TDS), please find attached responses to clarifications as received by 9<sup>th</sup> April, 2024.

Please note that the bid submission date remains 17<sup>th</sup> April, 2024 at 11:00 a.m. East Africa Time.



**ENG. JOSEPH KAMAU**  
**Ag. CHIEF EXECUTIVE OFFICER**

*Encl.*



PROCUREMENT OF WORKS FOR THE CONSTRUCTION OF WATER PROJECTS WITHIN AWWDA AREA OF JURISDICTION PHASE II: CONSTRUCTION OF GATUNDU NORTH AND LARI WATER SUPPLY PROJECT

TENDER NO.: AWWDA/GOK/GNL/W-19/2023-2024

RESPONSE TO CLARIFICATIONS SOUGHT BY BIDDERS



S/No.	Request for Clarification / Query	Response
1.	Bill No. 1: - PRELIMINARY AND GENERAL ITEMS - Items No. 104 and 105 - rate not matching with Amount	The corrected Bill No. 1 is hereby attached to this response
2.	Bill No. 2: - MBAUNI VILLAGE – Items No. 207, 208 and 209 - all valves same size	The corrected Bill No. 2 is hereby attached to this response
3.	Bill No. 4: - LOROMO, NYAMBARE & UPLANDS - Items No. 407, 408 and 409 - all valves same size	The corrected Bill No. 4 is hereby attached to this response

**BILL NO.1: PRELIMINARY AND GENERAL ITEMS**

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE (KSHS)	AMOUNT (KSHS)
101	<u>Contractor's Mobilization</u> Mobilization and demobilization of contractor's plant and equipment including but not limited to earthmoving units, pipe joining equipment, test pumping equipment, materials, personnel and other required supplies <u>Temporary Works</u>	LS	1		-
	<u>Contractor's Camp and Plant</u>				
102	Establish, maintain and remove Contractor's camps, offices, facilities, etc at the end of the contract.	LS	1		-
	<u>Project Sign Boards</u>				
103	Provide, erect and maintain project sign boards at borehole sites as directed by the Project Manager. The rate include installation, removal and storage as directed by Project Manager.	Nr	2		-
	—				
	<u>Provisional Sums</u>				
104	Allow Provisional Sum of Kshs 600,000.00 for maintaining, fuelling, lubricating and servicing of the transport vehicles assigned to the project for supervision of the works to be expended as directed by the Project Manager.	PS	1	600,000.00	600,000.00
105	Allow Provisional Sum of Kshs 600,000.00 to cover supervision costs of Engineers assigned on the project from the Employer's head office to cover expenses for communication, transport, allowances etc, to be expended as directed by the Project Manager.	PS	1	600,000.00	600,000.00
106	Allow Provisional Sum of Kshs 500,000.00 to cover the costs for branding, communicationa and visibility of project components to be expended as directed by the Project Manager.	PS	1	500,000.00	500,000.00
107	Allow Provisional Sum of Kshs 800,000.00 for fees requested by various authorities and agencies including TELECOM companies, road authorities etc.. This sum is to cover the identification and relocation of the said services.	PS	1	800,000.00	800,000.00

108	Add a percentage of items 105 to 109 for contractor's overhead profit.	%	10%	2,500,000.00	250,000.00
<b>BILL TOTAL FOR PRELIMINARY &amp; GENERAL CARRIED TO GRAND SUMMARY</b>					



**BILL NO. 2: MBAUNI VILLAGE**

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE (KSHS)	AMOUNT (KSHS)
	<b><u>Pipe Work - Supply, lay, joint, pressure test</u></b>				
	<i>Excavate pipe trench commencing from ground level to a minimum depth of 1.0 meter. Rate to include general bush clearing, laying the pipe and backfilling</i>				
	<b><u>Pipes</u></b>				
201	63mm Dia. HDPE PN 12.5 Pipes	M	3,000		
202	50mm Dia. HDPE PN 12.5 Pipes	M	2,800		
203	32mm Dia. HDPE PN 12.5 Pipes	M	3,000		
	<b><u>Pipe fittings</u></b>				
	<b><u>Couplings</u></b>				
204	63mm HDPE coupler	No	40		
205	50mm HDPE coupler	No	40		
206	32mm HDPE coupler	No	40		
	<b><u>Gate Valves</u></b>				
207	63mm Gate Valve	No	3		
208	50mm Gate Valve	No	6		
209	32mm Gate Valve	No	14		
	<b><u>End Caps</u></b>				
210	63mm End Cap	No	2		
211	50mm End Cap	No	4		
212	32mm End Cap	No	14		
	<b><u>Saddle Clamp</u></b>				
213	HDPE saddle clamp 63mm x 50mm	No	6		
214	HDPE saddle clamp 50mm x 32mm	No	8		
215	HDPE saddle clamp 63mm x 32mm	No	8		
216	HDPE saddle clamp 90mm x 63mm	No	1		
	<b><u>HDPE Tee</u></b>				
217	HDPE tee 63mm x 63mm	No	4		
218	HDPE tee 50mm x 50mm	No	2		
219	HDPE tee 63mm x 50mm	No	4		
220	HDPE tee 32mm x 32mm	No	4		
	<b><u>GI NIPPLE</u></b>				
221	32 mm nipple	No	16		
222	50 mm nipple	No	4		
	<b><u>HDPE ADAPTERS</u></b>				
223	HDPE male adapter 63mm	No	4		
224	HDPE male adapter 32mm	No	28		
225	HDPE male adapter 50mm	No	12		
	<b><u>HDPE REDUCER</u></b>				
226	HDPE reducer 63mm x 50mm	No	5		
227	HDPE reducer 50 mm x 32mm	No	4		
	<b><u>AIR VALVE</u></b>				
228	Air valve double orifice 50mm	No	3		
	<b><u>WATER METERS</u></b>				
229	water meters DN 15	No	750		
<b>BILL TOTAL FOR MBAUNI VILLAGE CARRIED TO GRAND SUMMARY</b>					

**BILL NO. 4: LOROMO, NYAMBARE & UPLANDS**

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE (KSHS)	AMOUNT (KSHS)
	—				
	<b><u>Pipe Work - Supply, lay, joint, pressure test</u></b>				
	<i>Excavate pipe trench commencing from ground level to a minimum depth of 1.0 meter. Rate to include general bush clearing, laying the pipe and backfilling</i>				
	<b><u>Pipes</u></b>				
401	63mm Dia. HDPE PN 12.5 Pipes	M	2,900		
402	50mm Dia. HDPE PN 12.5 Pipes	M	1,000		
403	32mm Dia. HDPE PN 12.5 Pipes	M	1,000		
	<b><u>Pipe fittings</u></b>				
	<b><u>Couplings</u></b>				
404	63mm HDPE coupler	No	35		
405	50mm HDPE coupler	No	12		
406	32mm HDPE coupler	No	12		
	<b><u>Gate Valves</u></b>				
407	63mm Gate Valve	No	4		
408	50mm Gate Valve	No	4		
409	32mm Gate Valve	No	10		
	<b><u>End Caps</u></b>				
410	63mm End Cap	No	4		
411	50mm End Cap	No	4		
412	32mm End Cap	No	4		
	<b><u>Saddle Clamp</u></b>				
413	HDPE saddle clamp 63mm x 32mm	No	4		
414	HDPE saddle clamp 50mm x 32mm	No	4		
415	HDPE saddle clamp 90mm x 63mm	No	2		
416	HDPE saddle clamp 90mm x 32mm	No	2		
	<b><u>HDPE Tee</u></b>				
417	HDPE tee 63mm x 63mm	No	4		
418	HDPE tee 50mm x 50mm	No	4		

	<b><u>GI NIPPLE</u></b>				
419	63 mm nipple	No	6		
420	50 mm nipple	No	4		
421	32 mm nipple	No	10		
	<b><u>HDPE ADAPTERS</u></b>				
422	HDPE male adapter 63mm	No	10		
423	HDPE male adapter 50mm	No	10		
424	HDPE male adapter 32mm	No	10		
	<b><u>HDPE REDUCER</u></b>				
425	HDPE reducer 63mm x 50mm	No	4		
426	HDPE reducer 90 mm x 63mm	No	1		
	<b><u>WATER METERS</u></b>				
427	water meters DN 15	No	500		
<b>BILL TOTAL FOR LOROMO, NYAMBARE &amp; UPLANDS CARRIED TO GRAND SUMMARY</b>					